SHIMOGA DIVISION.

ADVERTISEMENTS.

The 27th May 1891.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 10th June 1891, for re-constructing the Barr Lines at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1892.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A. M. and 5 P. M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory notes, as earnest money, and be superscribed "Tender for re-constructing the Barr Lines at Shimoga," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of Work.	Per.	Unit of Work.	Rate.
Dismantling present building	L. S.	..	
Excavation	C. Yd.	580	
Stone in mud	C. Ft.	32,120	
Brick in mud	C. Ft.	63,990	
Stone slabs	C. Ft.	1,290	
Do for floor, bath and privy	Do	3,510	
Teak wood poles squared	C. Ft.	1,380	
Roofing with teak reepers and Mangalore tiles	Sq.	365·00	
Mangalore ridge tiles	R. ft.	1,460	
Ventilating tiles	No.	100	
Sky lights	No.	100	
Pointing with mortar rough	Sq.	413·80	
Plastering with mortar	Sq.	39·80	
Whitewashing	Sq.	835·90	
Flooring with gravel	C. Yd.	310	
Jungle wood doors	S. Ft.	2,480	
Tarring	L. S.	..	

The 27th May 1891.

Subject to sanction by Government to the project notice is hereby given that sealed tenders separately for each of the channels will be received at the Office of the Executive Engineer, Shimoga Division, up to 15th June 1891, for improving Siddan and Basavan Channels of the Sulekere Lake of No. 356, Channagiri. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1893.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A. M. and 5 P. M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory notes, as earnest money, and be superscribed "Tender for improving Siddan and Basavan Channels," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of Work.	Per.	Quantity.	Rate.
Earthwork	C. Yd.	1,04,921	
Do soft rock	Do	1,353	
Do gravelly soil	Do	2,118	
Do filling	Do	2,134	
Do cutting	Do	8,696	
Rock cutting	Do	518	
Blastering rock	Do	455	
Puddling	Do	17,021	
Gravelling	Do	2,594	
Metalling	Do	68	
Filling leaks	L. S.	Rs	
Raising approaches	Do	Rs	
Jelly filling	C. Yd.	428	
Clearing site	L. S.	Rs	
Cutting distribution sluices	Do	Rs	
Jungle clearing	Do	Rs	
Turfing	Sqr.	5287·00	
Brick in mortar	C. Ft.	247·23	
Plastering with mortar	Sqr.	235·53	
Pointing with mortar	Do	83·60	
Concrete	C. Ft.	2,333	
Stone in mortar	Do	928	
Slab stone in mortar	Do	488	
Rubble stone in mortar, 1st sort	Do	4,093	
Do do 2nd sort	Do	9,085	
Ashlar work	Do	175	
Stone slabs, 3rd sort	Sqr. Ft.	6,729	
Do 2nd sort	Do	5,819	
Grooved slabs	At.	4	
Dressed raw stone work	C. Ft.	472	
Rough stone work (new)	C. Yd.	10,690	
Do (old)	C. Yd.	756	
Mile stones	At	10	
Furlong stones	Do	82	
Channel grade stones	Do	777	
Index stones	Do	184	
Guard stones	Do	44	
Survey charges	L. S.	Rs.	
Hutting	Do	Rs	
Baling water	Do	Rs	
Dismantling	Do	Rs	
Plug with rod complete	At	22	
Teakwood shutters	At	11	
Do work	C. Ft.	11	
Do do	Sft.	180	
Iron pipe 5" to 9" (diameter)	R. ft.	486	

B. S. VENKATACHARIYAR,
Offg. Executive Engineer, Shimoga Division.